



stella
1882



TECHNICAL PRESCRIPTIONS

Before installation and setting to work

Attention! The feeding pipes have to be rinsed carefully before the installation of the device so that there won't remain shavings, sealing or hemp residues, or other impurities inside the pipes. Through pipes not thoroughly rinsed or through the general water network, in the device foreign bodies can enter that could damage gaskets /o-ring. So filters should be installed also on the general system.

Max static pressure	10 Bar
Recommended working pressure*	1 - 5 Bar
* in order to fulfil the functional long life requirements listed by the standard EN817N	
Water temperature should not be higher than	70°C
Bacterial disinfection process	max. 70°C / 1 min.

TEKNISKA FÖRESKRIFTER

Innan installation och igångsättning

Se upp! Matnings rören måste sköljas ordentligt innan man installerar anordningen så att eventuella svetsrester, spån, hampa eller annat inte blir kvar inuti rören. Om rören inte sköljs ordentligt eller genom vattennätet kan smutspartiklar komma in i kroppen och skada packningen/o-ringen. Vi rekommenderar därför att förse huvudanläggningen med filter.

Statiskt tryck max	10 Bar
rekommenderat arbetstryck*	1 - 5 Bar
* för att uppfylla kraven på funktionell hållbarhet i enlighet med EN817N	
Vattentemperatur bör inte överstiga	70°C
Procedur för bakteriell desinfektion	max. 70°C / 1 min.